

2019 Construction Season Street Resurfacing Program

Street: Glenwood Road
Starts: Arrowhead Drive
Ends: Cul de sac

Reasons for inclusion in the Resurfacing Program:

- Poor pavement condition (Rating: 3 out of 10)
- Poor base leading to failing pavement: reconstructing with deeper removal and replacement to repair the base (Longer term repair)
- Pavement has uneven profile (Lots of dips and bumps): correcting with new paving work to provide smoother ride
- Requested by Streets and Sewers Division due to numerous water main breaks and problems with associated patching. Water main has now been all repaired and/or relocated.
- Last paved 1988 (31 years) according to best available records

Existing Road Photos:

